

BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer

Yelahanka Division

B.B.M.P. Bengaluru - 5A

No.EE/YNK-D/E-PMT/08/2016-17 Dated: 4-12-2017

APPROVED TENDER SCHEDULE -'B'

Item No: 33

Name of Work:-Providing pipe line in ward No- 02 of yelahanka Sub division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri G KISHORE NAIDU	
				Rate	Rate in Words
1	Cutting of road surface for pipeline trenches and disposing the excavated stuff as directed including barricading, danger lighting etc in the Cement Concrete Road (P.N. 264, I.N. 37.40)	Cum	216.00	566.00	Rupees five hundred sixty six only
2	Cutting of road surface for pipeline trenches and disposing the excavated stuff as directed including barricading, danger lighting etc in the Asphalt Surface Road (P.N. 264, I.N. 37.38)	Cum	126.00	317.00	Rupees three hundred seventeen only
3	KSRB 2-2.1 : Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No.5/Item No. 2.3)	Cum	1323.00	176.00	Rupees one hundred seventy six only
4	Providing and fixing to wall, ceiling and floor, medium density polyethylene pipes 6.00 kgs/sq.cm working pressure 75mm outside diameter with special flange, compression type fittings, wall clips , making good the wall, ceiling and floor including cost all material, labour charges, HOM of equipments and testing complete as per specifications.(P.N .93 I.N 13.70.3)	Rmtr	2850.00	281.00	Rupees two hundred eighty one or
5	Refilling available earth around pipelines, cables in layers not exceeding 20cms in depth compacting each deposited layers by ramming after watering lead upto 50m and lift upto 1.5m including cost of labour complete as per specification (P.No.6 I.No.2.11)	Cum	1323.00	70.00	Rupees seventy only

Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri G KISHORE NAIDU	
			Rate	Rate in Words
6 KSRB 13-6.3.1: Providing and fixing in position brass gate valve with C.I. wheel of approved quality (screwed end) 50 mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13.2.6 / 13.3 (Page No.92/Item No.13.37)	Each	35.00	1914.00	Rupees one thousand nine fourteen only
7 Providing and fixing on position brass bib cock of approved quality 25mm dia nominal bore including cost of all materials labour and HOM of equipments with all leads complete as per specifications.(P.N.91 I.N 13.25)	Each	175.00	253.00	Rupees two hundred fifty

K. Santhar Reddy
Signature of the Contractor

Santhar
Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.